

S.N.D.T. Women's University Sir Vithaldas Thackersey College of Home Science

(Autonomous)

NAAC Re-accredited 'A' Grade UGC Honor - College with Potential for Excellence



SVT/Quotation/2019-20/143

Date: 10.05.2019

SUB: Corrigendum of Quotation for Proposed Alteration And Renovation Work For Basment Room Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Madam /Sir,

Sealed quotations are invited for Proposed Alteration And Renovation Work For Basment Room Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai. Interested vendors are requested to submit their quote in the format given in Annexure A on company letter head. Quotation should be submitted to The Principal, Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai on or before 21st May, 2019 (before 4.00 p.m.)

Sir Vithaldas Thackersey College of Home Science (Autonomous), SNDT Women's University, Santacruz (West), Mumbai reserves the right to reject any or all quotations without assigning any reasons thereof.

Dr. Jagmeet Madan (Principal)

(Offer should filled on letter head) Annexure A

To,
The Principal,
Sir Vithaldas Thackersey College of Home Science (Autonomous),
SNDT Women's University,
Juhu, Santacruz (West),
Mumbai - 400 049.

SUB: Quotation for Proposed Alteration And Renovation Work For Basment Room Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Sir / Madam,

With reference to subject cited above we would like to furnish our quote with best rate possible as below :

SR.N O	PARTICULARS	UNITS	QTY	Per Sqft	AMOUNT
1	BASEMENT ROOM :-		CEO		
1.1	Breaking/Removing :- Existing Wall Plaster Breaking of Room	Sq.Ft	650 Sqft		
1.2	Plaster: - Providing & laying new plaster with sand and cement	Sq.Ft	650 Sqft		
1.3	Floor Polishing: - Machine cutting as per required, joints treated with neat cement slurry with an admixture of pigment to match the shade of stone for	Sq.Ft	350 Sqft		

	floor mirror polishing.					
4	Paint Work: Applying on wall three coats of Off white Plastic Paint of approved brand to give an even shade and colour after thoroughly brushing the surface, clean of all greaze and dirt, loose pieces of seals including preparing the surface with sand paper smooth (complete job including cost of	Sq.Ft	1000 Sqft			
	materials and labour)					
1.5	thk Polycap or comparable grade with comparable brand switches as specified by architect.					
	New electrical work done in 1.5mm thk Polycap or					
1.6	New electrical work done in 1.5 min things and new comparable grade wire for new light fittings and new comparable grade wire for new light fittings and new comparable grade wire for new light fittings and new comparable grade wire for new light fittings and new comparable grade wire for new light fittings.	Sq.Ft	550 Sqft			
	led ceiling light 11W 6ns as specified by architect.		Amo	ount (Rs.)		
	Add:- GST @ 18%					
	Total Amount (Rs.)					

All the terms and conditions given in notifications should be studied thoroughly and accepted fully.

Thanking you,

Yours truly,

Name of the Company Signature of the Proprietor Date:

Note: Please enclose 1. Self attested GST number copy,

- 2. Self attested PAN number copy, 3. Declaration on the company letter head if GST is not applicable.