



S.N.D.T. Women's University
Sir Vithaldas Thackersey College of Home Science
(Autonomous)

NAAC Re-accredited 'A' Grade
UGC Honor - College with Potential for Excellence



SVT/Quotation/2019-20/144


Date: 10.05.2019

SUB: Quotation for Proposed Alteration And Renovation Work For Basment Bathroom Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Madam /Sir,

Sealed quotations are invited for Proposed Alteration And Renovation Work For Basment Bathroom Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai. Interested vendors are requested to submit their quote in the format given in Annexure A on company letter head. Quotation should be submitted to The Principal, Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai on or before 21st May , 2019 (before 4.00 p.m.)

Sir Vithaldas Thackersey College of Home Science (Autonomous), SNDT Women's University, Santacruz (West), Mumbai reserves the right to reject any or all quotations without assigning any reasons thereof.


Dr. Jagmeet Madan
(Principal)

(Offer should filled on letter head)
Annexure A

To,
The Principal,
Sir Vithaldas Thackersey College of Home Science (Autonomous),
SNDT Women's University,
Juhu, Santacruz (West),
Mumbai - 400 049.

SUB: Quotation for Proposed Alteration And Renovation Work For Basment Bathroom Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Sir / Madam,

With reference to subject cited above we would like to furnish our quote with best rate possible as below :

SR.N O	PARTICULARS	UNIT S	QTY	RATE Per Sqft	AMOUNT
1	BASMENT BATHROOM :-				
1.1	Breaking/Removing :- All bathroom wall & floor tile and bathroom accessries.	Sq.Ft	330 Sqft		
1.2	Leveling Pcc work : Providing and laying Brick bat coba 9" deep and P/L sand and cement in the ratio of 6:1 for P.c.c work.	Sq.Ft	50 Sqft		

1.3	Waterproofing :- P / A Water-proofing treatment to bathroom area surfaces consisting of 2 coats of Dr. Fixit base coat to floors and vertical sides upto 900mm High from finish floor as under. 1st & 2nd coat of (Dr. fixit 301 Pidicrete URP) mixed with grey cement sealing all junctions, corners, joints of pipes and concrete.(allow for necessary curing and drying time of each coat, including surface preparation, cleaning the existing flooring, covering the waterproofing by plastering on top and bottom.	Sq.Ft	150 Sqft		
1.4	Wall Tiling : 1 x 1.5ft' , approximately 25mm thk tile fixing in bathroom, to be laid as per design, using 1:4 cement mortar, with machine cutting as required, joints treated with neat laticrete with an admixture of pigment as per drawing, to be laid as per plan complete, (gujarat tiles base rate 35/-)	Sq.Ft	330 Sqft		
1.5	Floor Tiling : 1 x 1.5ft' , approximately 25mm thk tile fixing in bathroom, to be laid as per design, using 1:4 cement mortar, with machine cutting as required, joints treated with neat laticrete with an admixture of pigment as per drawing, to be laid as per plan complete, (gujarat tiles base rate 35/-)	Sq.Ft	50 Sqft		
1.6	Plumbing :- PVC pipe of Prince or comparable brand, laying and looping for water supply with soil and drain pipes laid in slope for wet and dry areas of toilet.	Sq.Ft	1 Sqft		
1.7	Bathroom Accessories :- Providing & fixing bathroom accessories Jaqure brand fitting.	L/s	1 Sqft		12,000.00
2.1	Electrical Work :- New electrical work done in 1.5mm thk Polycap or comparable grade wire with ROMA or comparable brand switches as specified by architect.				
2.2	New electrical work done in 1.5mm thk Polycap or comparable grade wire for new light fittings as specified by architect.	L/s	1 Sqft		3,000.00
2.3	Paint Work :- Applying on wall three coats of Off white Plastic Paint of approved brand to give an even shade and colour after thoroughly brushing the surface, clean of all greaze and dirt, loose pieces of seals including preparing the surface with sand paper smooth (complete job including cost of materials and labour)	Sq.Ft	125 Sqft		
Amount (Rs.)					
Add:- GST @ 18%					
Total Amount (Rs.)					

All the terms and conditions given in notifications should be studied thoroughly and accepted fully.

Thanking you,

Yours truly,

Name of the Company
Signature of the Proprietor
Date :

- Note : Please enclose
1. Self attested GST number copy ,
 2. Self attested PAN number copy,
 3. Declaration on the company letter head if GST is not applicable.