

SVT/Quotation/2019-20/345


Date: 01.07.2019

SUB: Quotation for Costs of Repairing, Reconstructing, Maintaining the Inspection Chambers under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Madam /Sir,

Sealed quotations are invited for Costs of Repairing, Reconstructing, Maintaining the Inspection Chambers under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai. Interested vendors are requested to submit their quote in the format given in Annexure A on company letter head. Quotation should be submitted to The Principal, Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai on or before 09th July, 2019 (before 1.00 p.m.)

Sir Vithaldas Thackersey College of Home Science (Autonomous), SNDT Women's University, Santacruz (West), Mumbai reserves the right to reject any or all quotations without assigning any reasons thereof.


Dr. Jagmeet Madan
(Principal)

(Offer should filled on letter head)
Annexure A

To,
The Principal,
Sir Vithaldas Thackersey College of Home Science (Autonomous),
SNDT Women's University,
Juhu, Santacruz (West),
Mumbai - 400 049.

SUB: Quotation for Costs of Repairing, Reconstructing, Maintaining the Inspection Chambers under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Sir / Madam,

With reference to subject cited above we would like to furnish our quote with best rate possible as below :

ITEM NO.	DESCRIPTION OF ITEM	QTY	RATE (in Rs.)	UNIT	AMOUNT (in Rs.)
1	Providing & constructing INSPECTION CHAMBERS size :- 3'-0" x 1'-6" x depth as required for the slope with inside clear in 9" thk brick masonry using cement mortar (1:6), including earth excavation if needed, mass cement concrete (1:3:6) above 6" dry rubble packing to receive specified brick work, also including cement plaster 1:4 in two coats inside & outside and top of the wall, making 6" diameter half round channel finished with smooth cement ghutai complete with tothing in brick & mortar to receive precast concrete cover in each precast concrete frame connecting the channel to the related stoneware pipes carrying waste water drain & soil etc., all as per specifications & instructions.	4 Nos		Nos	
2	Repairing needed chambers shall be repaired with 3/4" thk cement mortar (1:4) plaster complete as per specifications & instructions.			Job	3,000/-
3	Providing & laying 4" thk cement concrete (PCC) above watered & rammed underneath debris for paved access, all as per specifications & instructions.	500 Sqft		Sqft	
4	Providing & laying kota tile on paved surface above concrete base & cement mortar (1:6) bedding as per specifications & instructions	250 Sqft		Sqft	
					Cont.2

5	Time & again checking & cleaning (minimum twice a month) all the 32 chambers surrounding the composite building at SNTD WU, Juhu, Mumbai. The cleaning should include related gully trap chambers also. (Quote charges per month cleaning twice for 12 months)				
	TOTAL	12 Months		Month	

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking you,

Yours truly,

Name of the Company
Signature of the Proprietor
Date :

- Note : Please enclose
1. Self attested GST number copy ,
 2. Self attested PAN number copy,
 3. Declaration on the company letter head if GST is not applicable.