



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Estate Dept./2019-20/ (Not. 01)/

July 04, 2019

Sub: Quotation of Nursery Civil work and drainage repairing at SNDT Laboratory, Nursery School, Department of Human Development at SNDT Women's University, Juhu Campus.

Madam/Sir,

Sealed quotations are invited for Nursery Civil work and drainage repairing at SNDT Laboratory, Nursery School, Department of Human Development at SNDT Women's University, Juhu Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 15Th July, 2019.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

(Dr. Deepak Deshpande)
Registrar



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Nursery Civil work and drainage repairing at SNDT Laboratory, Nursery School, Department of Human Development at SNDT Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No	Description	Qty	Unit	Rate	Amount
1	Supply of Mazdoor -Unskilled Heavy Male for removing of plaster.	5.00	Day		
2	Repair to RCC Damaged Members such a slab, beam, columns, by using Ready mix Polymer modified Mortar (upto20 mm thick). Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. and applying sulphate and choric free inorganic single component rust remover (RUSTICIDE- SUNANDA MAKE) confirming to IS 9077. The rusted surface shall become blackish non rusted colour. After 24 hours of application of rust remover, loose particles shall be removed by brush. Applying bonding coat slurry of high performance acrylic polymer modified mortar. Mix 1 kg Polyalk EP with 0.5 kg of cement, finish with ready to use repair polymer modified mortar (SUNMIX-SUNANDA MAKE) by adding 13-16% water by weight of SUNMIX for treatment to the damaged RCC members. Add 1kg or Bipolar Concrete Penetrating Corrosion Inhabiting Admixture POLYALK CP 293 per 25 kg bag of SUNMIX after mixing SUNMIX can be sprayed or trowel applied. When applying by hand SUNMIX must be forced tightly into the substrate to ensure complete contract with the substrate. Work shall be executed by certified	8.50	S.M.		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
	applicator only and work shall be guaranteed for 5 years and guarantee shall be provided on Rs. 500/- stamp paper (Excluding all taxes.)				
3	Providing internal cement plaster 25mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick or stone surface, in all positions including scaffolding and curing. Etc. complete.	12.00	S.M		
4	Providing second class Burnt Brick thick masonry with conventional I.S. type bricks in cement mortar 1:6 in superstructure including striking, joints, raking out joints, watering and scaffolding etc. complete.	1.50	S.M.		
5	Providing and laying telephone black/Amba White/Cadbury brown/Ruby red/Ocean Brown granite/stone of 18 to 20 mm thick for door frame/dado/window boxing etc. On C. M. 1:6 including filling joints with polymer base filler nosing the sharp edges wherever necessary, curing etc. complete.	6.50	S.M.		
6	Providing and fixing in position extruded aluminum door with fully aluminum composite panel having frame made out of extruded tubular section of size 50mm X 25 mm with 4 mm thick with aluminum composite panel fixed with P.V.C. cushioning beading as per approved drawing etc. complete.	9.00	S.M.		
7	Supply of Mazdoor – Unskilled Heavy Male for excavation work, extraction of tree bank, and removing of existing door frames etc. complete.	12.00	Day		
8	Providing dry/trap granite/quartzite/gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete,	3.500	CM		
9	Providing ad laying Cast in situ/Ready Mix cement concrete in M15 trap/granitee/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water. Steel centering, formwork, laying pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface only. Newly laid concrete shall be covered by gunny bag, plastic tarpaulin etc. (Wooden centering will not be allowed), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer concrete Batch mix	2.250	CM		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
	plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand/Crushed sand VSI Grade finely washed etc.)				
10	Scrapping the old plastered internet surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	135.00	S.M		
11	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make etc. complete.	100.00	S.M.		
12	Providing and applying priming coat on concrete masonry/Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	135.00	S.M.		
13	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface (excluding primer coat) etc. complete.	135.00	S.M.		
14	Providing and fixing flushing tank for W.C.(4 nos.) and bib cock or stop cock (4 nos.) with all fitting etc. complete.	1.00	L.S.		
15	Supply of Black Bakelite seat to European closer	4.00	No.		
16	Supply of Bib cock cock stop tap brass heavy 15 mm	5.00	No.		
17	"Providing and fixing decorative ceramic tiles of size 300 mm X 200 mm and above 5 to 6 mm thick for dado and skirting in required position fixed on plaster of cement mortar 1:4 neat cement paste, fitting joints with neat cement slurry, curing and cleaning complete."	10.00	SM		
18	Providing and laying ceramic tiles of having size 30 cm X 30 cm conforming to I.S. 15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	3.00	S.M.		
19	Replenishment/making up to lost area of reinforcement due to corrosion providing additional steel reinforcement. The steel shall confirm to IS 1786 grade Fe 415/Fe500 Anchor the steel rebar in sound concrete body up to desired depth to	40.00	Kg		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
	structural GRADE adhesive anchor fasteners fixing of rebar's is to be welded or binded by hinding wires to existing steel at regular grid as in compatibility to original design. Any additional space bars are welded to keep main reinforcement in perfect vertical position to keep the bar equidistant from center of gravity, minimum diameter of stirrups should be 8mm for columns and 10 mm for beams and maximum spacing should by 0.15 m C/C as directed by the structural Engineer and designed results, aligning be carried out with all the safety measures like helmet, safety belt and adequate labour insurance under the supervision of qualified supervisor etc. complete.(Excluding all taxes)				
20	Removing any kind of debris including loading in truck and conveying to approved dumping point beyond MCGM limits, unloading, spreading etc Complete (SSR Transportation Page No. 36) (Note: Rate to be reduced proportionately, if lead is within 50 km)	2.00	Cmt.		
	Total Amount				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable.