



S.N.D.T. Women's University
Sir Vithaldas Thackersey College of Home Science
(Autonomous)



NAAC Re-accredited 'A' Grade
UGC Honor - College with Potential for Excellence

SVT/Tender /2020-21/441


Date: 20th January, 2021

SUBJECT: Quotation for Repair and Renovation work for Cycle Room, Meter Room and Drainage Chambers under Sir Vithaldas Damodar Thackersey Charitable Trust grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Madam /Sir,

Sealed quotations are invited for Repair and Renovation work for Cycle Room, Meter Room and Drainage Chambers under Sir Vithaldas Damodar Thackersey Charitable Trust grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai. Interested vendors are requested to submit their quote in the format given in Annexure A on company letter head. Quotation should be submitted to The Principal, Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai on or before 02nd February, 2021 (before 4.00 p.m.)

Sir Vithaldas Thackersey College of Home Science (Autonomous), SNDT Women's University, Santacruz (West), Mumbai reserves the right to reject any or all quotations without assigning any reasons thereof.


Dr. Jagmeet Madan
(Principal)

(Offer should filled on letter head)
Annexure A

To,
The Principal,
Sir Vithaldas Thackersey College of Home Science (Autonomous),
SNDT Women's University,
Juhu, Santacruz (West),
Mumbai - 400 049.

SUBJECT: Quotation for Repair and Renovation work for Cycle Room, Meter Room and Drainage Chambers under Sir Vithaldas Damodar Thackersey Charitable Trust grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Respected Sir / Madam,

With reference to subject cited above we would like to furnish our quote with best rate possible as below :

ITEM NO.	DESCRIPTION OF ITEM	QTY	RATE (in Rs.)	UNIT	AMOUNT (in Rs.)
A	CYCLE ROOM				
1	Demolition of existing wall plaster as per instructions 10'-0" x 7'-0" x 2 = 140 Sqft 6'-0" x 4'-0" x 2 = 48 Sqft 5'-0" x 7'-0" x 1 = 35 Sqft 5'-0" x 3'-6" x 1 = 19.25 Sqft Ceiling (approx.) = 10 Sqft	250 Sqft	20	Sqft	
2	Providing & applying single coat cement mortar 1:4 plaster as per design, specifications & instructions.	250 Sqft	65	Sqft	
3	Providing & Fixing Ceramic tile dado including cement mortar backing on wall as per design & instructions	240 Sqft	135	Sqft	
4	Providing & Fixing Marble Shelves on wall as per specifications & instructions Basic price of Marble - Rs. 65/- per Sqft a) 10' x 1'-3" x 3 = 37.5 Sqft b) 6'-0" x 1'-3" x 3 = 22.5 Sqft c) 5'-0" x 1'-3" x 3 Sqft	79 Sqft	120	Sqft	
5	Providing & Laying 4" thk PCC (1:3:6) with Brick bat coba waterproofing on top as per instructions	80 Sqft	110	Sqft	
6	Providing & Laying 2'-0" x 1'-6" polished Kota tiles on top with cement mortar 1:4 bedding etc., complete with cement grouting Basic price of Kota - Rs. 55/- Sqft	80 Sqft	135	Sqft	

7	Providing & Fixing in position 4" Kotal tile skirting with cement mortar backing & jud work complete as per instructions	39 Rft	80	Rft	
8	Providing & Fixing Kota slab Jamb in two pieces for Door opening to receive door shutter as per instructions.	16.5 Rft	200	Rft	
9	Proposed Refurbishing of existing Door with 4mm thk ply covering to have 1mm thk laminate sheet of approved make & shade as per instructions Size: 2'-6" x 6'-9"	1 No.	8000	Nos.	
10	Providing & Applying Plastic Emulsion Paint to ceiling in 3 coats as per instructions	80 Sqft	17	Sqft	
11	Electrical Work	P.S			
B	METER ROOM				
12	Excavation in Meter room by removing aggregate packing upto 4'-4", laying Concrete PCC & packing in 4" layers to conceal the cables at required level as instructed by Electrician of College etc., complete (1:3:6 lower base & 1:2:4 upper layer)	180 Sqft	250/-	Sqft	
13	Brick wall along the common room & below the meters & main switches for 4'-3" level on MCC base wall in cement mortar (1:5) with entry side plaster with waterproofing compound as per instructions	P.S			10,000/-
14	Providing & Laying Brick bat coba in passage including PCC & kota tile on base as per instructions	30 Sqft	220/-	Sqft	
C	DRAINAGE CHAMBERS				
15	Existing Inspection Chamber to be blocked with debris & PCC as per instructions	P.S			1,000/-
16	Proposed Inspection Chamber size internally 3'-6" x 1'-6" x 4'-3" deep in 9" brick work, PCC bed in (1:3:6) with half round channel including, cement mortar plaster in 2 coats, C.I frame & cover as per instructions	1 No.	20000/-	Nos	
17	Removal of choked pipes & laying new stoneware drain pipe on PCC bed & cement jointed, also laid to slope as per instructions (Basic price of Pipe - Rs. 170/-)	48 Rft	400/-	Rft	
	TOTAL				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking you,

Yours truly,

Name of the Company

Signature of the Proprietor

Date :

- Note : Please enclose
1. Self attested GST number copy ,
 2. Self attested PAN number copy,
 3. Declaration on the company letter head if GST is not applicable.