

SNDT Women's University

1, Nathibai Thackersey Road, Mumbai 400 020

Phone: +91 22 2203 1879 Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ १, नाधीबाई डाकरसी गार्ग भुंबई ४०० ०२० Telegram: UNIWOMEN Website: sndt.ac.in

Estate Dept./2021-22 /(Not.2)/10

April 20, 2021

Sub: Quotation for Plaster work and plum concreting work for storm water drain line around big ground at SNDT Women's University, Juhu Campus...

Madam/Sir,

Sealed quotations are invited for Plaster work and plum concreting work for storm water drain line around big ground at SNDT Women's University, Juhu Campus.. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the Office of "The Registrar" at Churchgate campus on or before 30th April 2021 Contractor should submit their.

- i) GST No.
- ii) PAN no.
- iii) Client List,
- iv) Company profile,
- v) Last 3 years audited profit lost statement along with Quotation

Quotation should be submitted in closed envelop and on top write the subject.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

(Dr. Meera Desai

Registrar(Addl.Charge)

SNDT Women's University

1, Nathibai Thackersey Road, Mumbai 400 020 Phone: +91 22 2203 1879 Pax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ १, नाधीबाई ठाकरथी गार्ग मुंबई ४०० ०२० Talegram: UNIWOMEN Website: sndt.ac.in

(Offer should filled on letter head)

Annexure A

To, The Registrar SNDT Women's University, Churchgate, Mumbai

Sub: Quotation Plaster work and plum concreting work for storm water drain line around big ground at SNDT Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of Item	Qty	Unit	Rate	Amount
01	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	150.00	Sqm.		
02	Providing and laying in position in situ PLUM CONCRETE, M-15 grade using trap metal, rubble stone (size 100 mm to 200 mm) & River sand with minimum cement content as per approved mix design as per IS 456-2000 by Engineer- in charge for foundation and bedding including admixturesto accelerate, retard setting of concrete to improve workability without impairing strength and durability. The rates shall includes bailing out water manually centering. Shuttering , compacting by vibrator and curing (Excluding reinforcement) etc. Complete.	29.00	Cum.		
03	Providing manually cleaning to storm water drain line with the help of required tools for proper functioning line and stacking the same in as directed etc. complete.	320.00	Rmt.		
	Total				

SNDT Women's University

1. Nathibai Thackersey Road. Mumbai 400 020 Phone: +91 22 2203 1879 Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापी_ट १, बाधीबाई ठाकरसी मार्ज सुंबई ४०० ०२० Telegram: UNIWOMEN Website: andt.ac.in

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable