

SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Dept./2022-23/239

August 24, 2022

SUB: Quotation for Repair & Renovation work of Gym for Student Home building at S.N.D.T. Women's University, Pune Campus.

Madam/Sir,

Sealed Quotations are invited for Repair & Renovation work of Gym for Student Home building at S.N.D.T. Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **12th Sep 2022** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope, financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

a) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant


b. b) Financial Bid

- i. Mentioning including all taxes
- ii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,


(Dr. Vandana Sharma)
Registrar (Addl. Charge)
SNDT Women's University
Mumbai - 20.

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repair & Renovation work of Gym for Student Home building at S.N.D.T. Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

<u>Sr. No.</u>	<u>Description of Item</u>	<u>Qty</u>	<u>Unit</u>	<u>Rate</u>	<u>Amount</u>
1	Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.	43.00	Cum.		
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. Note : Following items to be executed after prior approval of Superintending Engineer.	117.00	Sqm.		
3	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	88.00	Sqm.		
4	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	8.00*	No.		
5	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materials out side etc. carefully and throwing out the refusal outside etc. complete.	3.00	No.		
6	Providing and laying Cast in situ/Ready Mixcement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork,	4.00	Cum.		

	laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (crushed sand VSI Grade)				
7	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	20.00	Sqm.		
8	Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1 Kg per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete.	183.00	Sqm.		
9	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing (and filling joints of Nahani trap and any outlet by properly) etc. complete.	71.00	Sqm.		

10	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	106.00	Sqm.		
11	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with rounding the edges etc. complete. One side polish	10.00	Sqm.		
12	Providing and laying ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	21.00	Sqm.		
13	Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	67.00	Sqm.		
14	Providing and Fixing 32mm thick One piece single moulded puff ABSTRONE BUTADYNE STYRINE(ABS) Door Shutter for internal use including toilets made up of outer ABS sheet of 1.2mm thick having puff insukation of 35 to 40Kg/Cum.density and 10mm dia.for steel bars2 Nos.,wooden clock to recive fixtures, having M.S.hinges 100mm length M.S. handles 150mm length and 10mm dia sliding door bolt etc. complete	7.00	Sqm.		
15	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	21.00	Rmt		
16	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc.	43.00	Rmt		

	complete.				
17	Providing and fixing Oval Type Under Counter Wash Hand Basin of 420 X 590 X 195mm size with pillar cock, C.P. Angular stop cock, long thread of approved make continental including SS bottle trap of necessary pipe connection up to the outside face of the wall, having Telephonic Black/colour Granite of 180mm thick fixed on Black Kadappa Frame work, etc Complete as directed by Engineer in charge.	2.00	No.		
18	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.	5.00	Sqm.		
19	Providing and fixing 8 cm rigid PVC Nahani trap including PVC grating ,bend,connecting piece of UPVC pipe up to the outside face of wall ,making the good damaged surface and testing etc. complete (Prior approval of sample and brand by Ex. Engr. is necessary before use)	6.00	No.		
20	Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete. (The contractor shall give 3 yrs guarantee bond for payment)	54.00	Rmt		
21	Providing and fixing C.P. BIB cock with wall flange jaquar or equivalent make continental (CAT.NO. CON-047) including necessary sockets/ union nut etc. complete.	6.00	No.		
22	Providing, laying and fixing P.V.C. pipe of 75mm dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc.	18.00	Rmt		

	complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.				
23	Providing and applying Two coats of wall care Putty of 2mm thickness for plastered surface and 5-6mm thickness finished concrete surface to Ceiling and Walls to prepare surface even and smooth of Brands BIRLA WHITE, BERGER, BISION, J.K., make, etc complete. a) For plastered walls/ceiling 2mm	462.00	Sqm.		
24	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc.complete as directed	462.00	Sqm.		
25	Removing old paint from steel and other metal surfaces and making the surfaces even with hand scrapping, scaffolding etc. complete.	113.00	Sqm.		
26	Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below Scrapping for surface with emery paper and wipe clean for area. Applying Asian/ Berger/Nerolac/ Dulux Paints or equivalent wall primer with brush by adding mineral turpentine oil by 8 to 10% or water by 15 to 20 % allowing to dry for 6 to 8 hour After applying Asian/ Berger/Nerolac/ Dulux Paints or equivalent acrylic wall putty with appropriate proportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royal Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70 % by role Applying paints Royal luxury emulsion 2nd coat with brush with water content 40 to 45 % or 65 to 70% by roller.(with prior approval of S.E.)	462.00	Sqm.		
27	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	113.00	Sqm.		
	Net Total				
	Add GST as Applicable				
	Total				