

SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Dept./2022-23/ 194

July 26, 2022

SUB: Quotation for Repairs and renovation work of canteen building at SNDT Women's University, Pune Campus.

Madam/Sir,

Sealed Quotations are invited for Repairs and renovation work of canteen building at SNDT Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **05 August 2022**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope, financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

a) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

b. b) Financial Bid

- i. Mentioning including all taxes
- ii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Share

(Signature)

(Dr. Vandana Sharma)
Registrar (Addl.Charge)

(Offer should filled on letter head)
Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repairs and renovation work of canteen building at SNDT Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

<u>Sr. No.</u>	<u>Description of Item</u>	<u>Qty</u>	<u>Unit</u>	<u>Rate</u>	<u>Amount</u>
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	173.00	Sqm.		
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. Note: Following items to be executed after prior approval of Superintending Engineer.	145.00	Sqm		
3	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	6.00	No		
4	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed con-crete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materiasls out side etc. carefully and throwing out the refusal outside etc. complete.	3.00	No.		
5	Excavation for foundation in earth, soils of all types, sand,gravel and soft murum, including removing the excavated material upto a distance of 50 meters beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means	36.00	Cum		
6	Providing and laying Cast in situ/Ready Mix cement	15.00	Cum		

	concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, plywood/steel formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand				
7	Providing and fixing 8 cm rigid PVC Nahani trap including PVC grating ,bend, connecting piece of UPVC pipe up to the outside face of wall ,making the good damaged surface and testing etc. complete (Prior approval of sample and brand by Ex. Engr. is necessary before use)	6.00	No.		
8	Providing and fixing orissa type colour glazed earthenware 625 x 450 mm. w.c. pan including trap, C.I. soil and vent pipe upto the out side face of wall including 100 mm. dia. C.I. plug, bend, 15mm. thick 10 litre PVC flushing cistern with all necessary pipe connection etc. complete.	3.00	No.		
9	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	20.00	Smt		
10	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing (and filling joints of Nahani trap and any outlet by properly) etc. complete.	66.00	Sqm		
11	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with rounding the edges etc. complete. One side polish	10.00	Sqm		
12	Providing and laying Polished Tandur Stone flooring 25mm to 30mm thick required width in plain/	96.00	Sqm		

	pattern on a bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.				
13	Providing and laying ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	21.00	Sqm		
14	Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	67.00	Sqm		
15	Providing and fixing coloured glazed earthenware Wash Hand Basin of 55cm x 40 cm size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	4.00	No		
16	Providing and fixing 32 mm thick one piece single moulded puff ABSTRONE BUT ADYNE STYRINE (ABS) Door shutter for internal use including toilets made up of outer ABS sheet of 1.2 mm thick having puff insulation of 35 to 40 kg/Cum. Density and 10 mm dia. For steel bars 2 Nos., wooden block to receive fixtures, having M.S. hinges 100mm length, M.S. handles 150 mm length and 10 mm dia sliding door blot.etc.	10.00	Sqm		
17	Providing and laying concrete pipes of I.S.NP. class of 150mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete.	40.00	Rmt		
18	Providing and constructing Brick Masonry inspection trap Chamber 90cm x 45cm including 1:4:8 C.C foundation, 1:2:4 C.C.channels/half round glazed stoneware pipe channel, salt glazed stone-ware intercepting trap with rodding pipe set in 1:4:8 cement concrete block, brick masonry plastering inside and Outside, fixed in cement concrete with R.C.C. Cover medium duty 140 kg. etc complete.	3.00	No		
19	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	11.00	Cum		
20	Providing dry/ trap/ granite/ quartzite/ gneiss rubble	18.00	Cum		

	stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.				
21	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	47.00	Sqm		
22	Machine polishing to cement/marble mosaic tiled flooring or any other type of flooring including cleaning, washing, etc. complete.	117.00	Sqm		
23	Providing and Applying royale luxury emulsion of approved make on internal wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hours after applying acrylic wall putty with appropriate proportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean applying paints Royale Luxury emulsion 1 st coat with brush water content water 40 to 45 % or 65% to 70 % by roller (with prior approval of S E)	550.00	Sqm		
24	Removing old paint from steel and other metal surfaces and making the surfaces even with hand scrapping, scaffolding etc. complete.	113.00	Sqm		
25	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	113.00	Sqm		
26	Providing, laying and fixing P.V.C. pipe of 75mm dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	16.00	Rmt.		
27	Providing and fixing C.P. BIB cock with wall flange jaquar or equivalent make continental (CAT.NO. CON-047) including necessary sockets/ union nut etc. complete.	6.00	No		
	Net Total				
	Add GST as Applicable				
	Total				