


SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Dept./2022-23/83

May 18, 2022

SUB: Quotation Repair to drainage pipe line & flooring work of toilet block room no. 3 & passage W. C. of ground floor of guest house at S.N.D.T. Women's University, Pune Campus.

Madam/Sir,

Sealed Quotation are invited for Proposal for Repair to drainage pipe line & flooring work of toilet block room no. 3 & passage W. C. of ground floor of guest house at S.N.D.T. Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **28th May 2022**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope, financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

a) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate (not only the client list)
- iii. Registration Certificate
- iv. GST Certificate
- v. PAN Copy
- vi. If GST is not applicable then declaration of the same.
- vii. If any work which requires specific expertise/ technical specifications then the same should be mentioned.
- viii. Audited Financial Statements for last three years .(Income Tax)

b. b) Financial Bid

- i. Mentioning including all taxes
- ii. If required component wise then format to be given component wise
- iii. Terms and condition of contract.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Sharma
20/5/22

(Dr. Vandana Sharma)
Registrar (Addl.Charge)

[Handwritten signature]

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repair to drainage pipe line & flooring work of toilet block room no. 3 & passage W. C. of ground floor of guest house at S.N.D.T. Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

<u>Sr. No.</u>	<u>Description of Item</u>	<u>Qty</u>	<u>Unit</u>	<u>Rate</u>	<u>Amount</u>
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete.	114.00	Sqm		
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. Note : Following items to be executed after prior approval of Superintending Engineer.	30.00	Sqm		
3	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	4.00	No		
4	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed con-crete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materiasls out side etc. carefully and throwing out the refusal outside etc. complete.	2.00	No		
5	Removing brick bat coba including stacking the spoils as directed with all leads, lifts etc,	7.00	Cum		

	complete.				
6	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	7.00	Smt.		
7	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing (and filling joints of Nahani trap and any outlet by properly) etc. complete.	30.00	Sqm		
8	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with rounding the edges etc. complete. One side polish	5.00	Sqm		
9	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, plywood/steel formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	6.00	Cum		
10	Providing and laying vitrified matt fininsh tiles having size 590 mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement morar including neat cement float, filling	26.00	Sqm		

	joints, curing and cleaning etc. complete. a) Flooring				
11	Providing and fixing 8cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete.	4.00	No.		
12	Providing and fixing 1st class white glazed earthenware Orissa Type W.C. Pan 580 mm dia including P or S trap cast iron soil and vent pipe upto the outside face of the wall (1:5:1 0) cement concrete bedding 15 mm thick, 10 liter P.V.C. flushing cistern with all necessary pipe connection etc. complete.	1.00	No		
13	Providing and fixing European type white glazed earthenware water closet pan with UPVC seat and lid with chromium plated brass hinges and rubber buffers including UPVC and vent pipe up to the outside face of wall without flushing cistern with flush cock and with water Jet and necessary fittings including cutting and making good to the walls and floors testing etc. complete.(prior approval of sample and brand by Ex. Engineer is necessary before use)	1.00	No		
14	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	18.00	Rmt		
15	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	26.00	Rmt		
16	Providing and laying ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	18.00	Sqm		
17	Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade	35.00	Sqm		

	adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.				
18	Providing and Fixing 32 mm thick One piece single moulded puff ABSTRONE BUTADYNE STYRINE (ABS) Door shutter for internal use including toilets made up of outer ABS sheet of 1.2 mm thick having puff insulation of 35 to 40 Kg/Cum.density and 10 mm dia.for steel bars 2 Nos., wooden block to receive fixtures, having M.S. hinges 100 mm length, M.S. handles 150 mm length and 10 mm dia sliding door bolt etc. complete	5.00	Sqm		
19	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.	3.00	Sqm		
20	Providing and constructing Brick Masonry inspection trap Chamber 90cm x 45cm including 1:4:8 C.C foundation, 1:2:4 C.C.channels/half round glazed stoneware pipe channel, salt glazed stone-ware intercepting trap with rodding pipe set in 1:4:8 cement concrete block, brick masonry plastering inside and Outside, fixed in cement concrete with R.C.C. Cover medium duty 140 kg. etc complete	7.00	No		
21	Providing and laying concrete pipes of I.S.NP. class of 150mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete.	97.00	Rmt		
22	Excavation for foundation in earth, soils of all types, sand,gravel and soft murum, including removing the excavated material upto a distance of 50 meters beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means	122.00	Cum		

23	Lowering down the debris obtained from breacking and removing the cement plaster/ burnt brick masonry of the first floor by any means without casuing dust nuisance and damage to structure, saking the same as and whrer diected incliding cleaning the site.complete.	19.00	Cum		
24	Lobour Charges for site cleaning	12.00	No		
25	Labour charges for refixing boiler.	9.00	No		
26	Providing and applyning Royale Laxury Emulsion of of approved make on internal wall surface as detiled below Scrapping for surface with emey paper and wipe clean for area. Applyning Asin/ Berger/ Nerolac/DULuc Paints or equivalent wall prime with brush by adding mineral turpentine oil by 8 to 10% or water by 15 to 20% allowning to dry for 6 to 8 hourts after by 15 to 20% allwing to dry for Asian/ Berger/Nerolac/Dulux Paints or equivalent acrylic wall putty with appropriate propotion of water of allow to dry for period of 4 to 6 hours activity.Scrapping with emery paper and wipe clean Applyning paints royle Luxury emusion 1 st coat with brush water content water 40 to 45% or 65 to 70% by role Applyning paints Royle Laxury emulsion 2 nd coat with brush with water content 40 to 45% or 65 to 70% by roller. (with prior approval of S.E.)	78.00	Sqm		
	Net Total				
	Add GST as Applicable				
	Total				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable.

