



Estate Dept./2022-23/450

January 25, 2023

SUB: Quotation for laying of Trimix / VDF Flooring with design on entrance of composite building at S.N.D.T. Women's University, Juhu Campus

Madam/Sir,

Sealed quotations are invited for laying of Trimix / VDF Flooring with design on entrance of composite building at S.N.D.T. Women's University, Juhu Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before 08 February, 2023 Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

a) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

b) Financial Bid

- i. Mentioning including all taxes
- ii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavekar

Registrar

Registrar

**SNDT Women's University
Mumbai - 20**

(Offer should filled on letter head)
Annexure A

To,

The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for laying of Trimix / VDF Flooring with design on entrance of composite building at S.N.D.T. Women's University, Juhu Campus

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No	Description of Item	Qty	Unit	Rate	Amount
1	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	33.00	Cum		
2	Finishing upto 225 mm thick cement concrete laid to proper level and slope including compacting finishing with tremix treatment for paving slab with compaction by screed vibrator , removing excess water from the cement concrete by tremix vaccum dewatering system , finishing the surface with floater and trowel including all etc. complete as directed	190.00	Smt		
3	Providing, applying and finishing the top surface of M-20concrete with stamp/stencil of approved pattern and colour, in accordance with manufacturer's specification of any approved brand of colour hardener @ of 3.5 kgs/m ² ; including floating of colour hardened over concreate surface with different types of floaters ;incuding application of release agent @ of 0.15 kgs/m ² , stamping over the concrete surface with stamping tools; including	190.00	Smt		

	cleaning of surface with water and cutting of finished concrete ; including application of two coats of acrylic based sealer for finishing. Colour hardener and release agent shall be tested for abrasion resistance for a depth of water, should not be more than 0.025mm. coverage of seal should not be more than 6.5sqm per one litre coat; including cost of skilled manpower, cutting machine, sprayer and all tools trackles for all activities; complete smooth & finish as per direction of Engineer-in-charge.			
4	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	1.50	M.T.	
5	Providing and fixing reinforced cement concrete cover of size 90 cm x 45 cm with frame over inspection chamber etc. complete. Heavy duty (225 Kilogram)	2.00	No.	
6	Providing, laying and fixing P.V.C. pipe of 110 mm. dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	Rmt.	
	Net Total			
	Taxes will be paid at actual at the prevailing time.			
	Total			

