

SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Section/2023-24/390

January 15th, 2024

SUB: Quotation for Repairing work of west side staircase area from ground floor to 7th floor level in main building at S.N.D.T. Women's University, Churchgate Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Repairing work of west side staircase area from ground floor to 7th floor level in main building at S.N.D.T. Women's University, Churchgate Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **01st, February 2024**

Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant


B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,


Prof. Vilas D. Nandavadekar

(Offer should filled on letter head)

Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repairing work of west side staircase area from ground floor to 7th floor level in main building at S.N.D.T. Women's University, Churchgate Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the derbis upto a distance of 50 meters or spreading in the compound and cleaning the site etc. Complete.	178.00	Sqm		
2	Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. And applying sulphate and chloride free inorganic single component rust remover Rusticide as approved by Engineer in charge conforming to IS 9077. The rusted surface shall become blackish non rusted colour. After 24 hours of application of rust remover, loose particles shall be removed by brush. Apply one more coat of Rusticide. Apply bonding coat slurry of high performance acrylic polymer Methy 1 2-methy1propenoate copolymer with another enoate as approved by Engineer in charge on entire surface . Mix 1 kg of acrylic polymer with 0.5 Kg of cement. Finish it with ready to use repair polymer modified mortar based on special cements, aldehyed based polymers with thixotropy modifying agents as approved by engineer in charge (The polymer Modified Mortar (PMM) should attain min. Compressive strength of 20 N/mm2 in 1 day and 30 N/mm2 in 7 days) by adding 13-16% water by weight of polymer modified mortar for treatment to the damaged RCC members. Add 1 kg of Migrating Corrosion Inhibiting Admixture as	178.00	Sqm		

	approved by Engineer in charge per 25 Kg bag of polymer modified mortar, it can be trowel applied or sprayed . When applying by hand , polymer modified mortar must be forced tightly into the substrate to ensure complete contact with the substrate. (15 mm to 30 mm thickness at a time)				
3	Repair with Microconcrete : Providing mixing and placing 100 mm thick encasement with free flow high performance micro-concrete as per technical specification. (Note :- This rate is for 100 mm thickness during execution, if thickness is reduced rete to be redused accordingly)	1.75	Sqm		
4	Providing and fixing in position TMT -FE - 500 bar reinforcement of various diameters for R.C.C. Pile caps, footings, foundation slabs, beams column , canopies , staircase, newels, chajjas, lintels pardis , copings, fins, arches etc. As per deatiled designs, drawing and schedules including cutting , bending , hooking the bars , binding with wires or tack welding and suporting as required complete.	0.50	MT		
5	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces, in all position including scaffolding and curing etc. Complete	178.00	Sqm		
6	Providing and applyong two coats of wall care putty on plastered surface and ceiling and walls to prepare surface even and smooth of approved make, etc complete .	655.18	Sqm		
7	Providing and applying priming coat on concrete / masonry / Asbestos cement plastered surfaces including scaffolding in neccessary , preparing the surface by thoroughly cleaning oil , grease, dirt and other foreign matter and papering as required etc. complete.	819.00	Sqm		
8	Providing and applying priming coat over new wood and wood based surfaces, including preparing the surface by throughly cleaning oil, grease , dirt and other foreign matter, sand papering and knotting , scaffolding etc. Complete.	292.59	Sqm		
9	Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work previously painted in building including scaffolding , if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete	292.59	Sqm		
10	Providing and applying plastic emulsion paint of approved quality , colour and shade to new surface in three coats including scaffolding ,	819.00	Sqm		

	preparing the surface . (excluding primer coat) etc. Complete.				
11	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete.	12.00	CM		
12	Providing and applying hand for required finish on previously polished wood including knotting , preparing the surfaces, scaffolding etc. Complete as directed	27.44	Sqm		
13	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building / structure, including additional rows of scaffolding in stepped manner as per requirement of site , made with 40 mm dia M.S. Tube, placed 1.5 meter center to center , horizontal & vertical tubes , joint with cup & lock system with M.S. Tubes, M.S. tube chalis , M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and / or pointing and / or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracing , sunners, connecting with the building etc, wherever required , if feasible , for inspection of work at required location with essential safety features for the workmen etc., complete as per direction and approval of engineer-in-charge. Note :- (1) the elevation area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	215.00	Sqm		
14	Removing and kind of debris including loading in truck and conveying to dumping point approved by MCGM , unloading , spreading etc. Complete with all leads and lifts.	12.00	CM		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				