

3rd Floor, P. V. Polytechnic Building,  
Sir Vithaldas Vidya Vihar, Juhu Road,  
Santacruz (West), Mumbai - 400 049.



**Mr. Dinesh Girap**  
Director (Addl. Charge)

Subject: Invitation for Quotation refurbishment of CAD CAM LAB for Centre for Vocational & Technical Education, SNDT Women's University, Juhu Campus, Mumbai.

Respected Sir/Madam,  
Quotations are invited from Proprietorship/ Partnership/ Private Limited firms for providing of Refurbishment of CAD CAM LAB at 3<sup>rd</sup> floor in JDM Dept. in C.V.T.E., SNDT Women's University, Juhu Campus, Mumbai.

Name of the Item	Refurbishment of CAD CAM LAB at 3 <sup>rd</sup> floor in JDM Dept.
Venue of Submission	CVTE. P. V. Polytechnic Building, SNDTWU Campus, Santacruz (west), Mumbai 400049
To be Addressed to	Director, CVTE, SNDTWU Campus, Santacruz (west), Mumbai 400049
GST NO.	27AACT52211D1Z0
Contact Number	9821304258
Deadline	24/11/2024 till 4 pm

Quotations are invited in 3 envelop system. Sealed envelope no.3 will contain two envelopes- Envelop No.1 and 2. Envelop No.1 is technical quotation and it will be opened first and if it contains all the required papers then only the Envelop No.2 containing schedule of rates shall be opened. If it is found that all the papers are kept in one envelop ignoring the instructions given above, the quotation may be rejected.

**Envelop No.1 (Technical Bid)**


1. Detail Information about organization, Name of Proprietor, Telephone Number. In case of Partnership firm- Name and address of Partners and Partnership Deed
2. Certified copy of GST Registration. (If not applicable Declaration) Is to be attached.
3. Copy of Pancard of Proprietor/Firm
4. Type of Business entity: Manufacturer / authorized dealer, any other (to be specified)
5. Copies of technical specification of all the items.
6. Work experience in civil work. (Prof to be attached).

**Envelop No.2 (Financial Bid)**

1. Duly filled quotation as per specification mentioned in Annexure I.

**General Instructions:**

1. Rate must be inclusive of all the charges. Taxes must be mentioned clearly in the quotation.
2. If GST is not applicable, kindly specify it clearly in the quotation.
3. Once a rate is fixed, it shall remain same and must not be subject to escalation whatsoever be the reason during the contract.
4. Vendor should adhere with all the seriousness to the time schedule provided by the institute.
5. Payment will be made after successful completion of the work after 15 days of tax invoice. No advance payment will be made.
6. Institute reserves the right of canceling the quotation invitation.
7. Successful bidder must adhere to the specifications and standards mentioned in the document.
8. Vendor should visit to the site personally, if any query.
9. TDS will be deducted as per the rule.
10. Site inspector will be allowed with the prior appointment.

  
Mr. Dinesh Girap  
Director (Addl. Charge)





## ANNEXURE I

**Name of Item:** Refurbishment of CAD CAM LAB at 3rd floor in JDM Dept., at PV Polytechnic building SNDT Women's University, Juhu Campus, Mumbai.

### FINANCIAL BID.

Sr. No		Description of Item	Rate	Unit Per	Amount
6.00 Square Metres	1.	Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. and applying sulphate and chloride free inorganic single component rust remover Rusticide as approved by Engineer in charge conforming to IS 9077. The rusted surface shall become blackish non rusted colour. After 24 hours of application of rust remover, loose particles shall be removed by brush. Apply one more coat of Rusticide. Apply bonding coat slurry of high performance acrylic polymer - Methyl 2-methylpropenoate copolymer with another enoate as approved by Engineer in charge on entire surface. Mix 1 Kg of acrylic polymer with 0.5 Kg of cement. Finish it with ready to use repair polymer modified mortar based on special cements, aldehyde based polymers with thixotropy modifying agents as approved by Engineer in charge (The Polymer Modified Mortar (PMM) should attain min. compressive strength of 20 N/mm <sup>2</sup> in 1 day and 30 N/mm <sup>2</sup> in 7 days) by adding 13 - 16% water by weight of polymer modified mortar for treatment to the damaged RCC members. Add 1 Kg of Migrating Corrosion Inhibiting Admixture as approved by Engineer in charge per 25 Kg bag of polymer modified mortar. After mixing polymer modified mortar, it can be trowel applied or sprayed. When applying by hand, polymer modified mortar must be forced tightly into the substrate to ensure complete contact with the substrate. (Upto 15mm thickness at a time). (SSR 2022-23/52.35) Add 5% For Corpn.			
		Total		Sqm.	
10.00 Square Metres	2.	Removing the existing cement plaser of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. (SSR 2022-23/32.33) Add 5% For Corpn.			
		Total		Sqm.	
10.00 Square Metres	3.	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete. (SSR 2022-23/32.03) Add 5% For Corpn			
		Total		Sqm.	
50.00	4.	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete			



Square Meters		including stacking the materials as directed with all leads, lifts etc. complete. (SSR 2022-23/46.19) Add 5% For Corpn.			
		Total		Sqm.	
10 Days	5.	Supply of Mazdoor - Unskilled Heavy Male for removing existing platform. (SSR 2022-23/ I-Labour36)		Day	
5.00 Cubic Metres	6.	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc. (SSR 2022-23/46.09) Add 5% For Corpn.			
		Total		Cum.	
16.00 Cubic Metres	7.	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete. (SSR 2022-23/I-46.59)		Cum.	
16.00 Cubic Metres	8.	Removing any kind of debris including loading in truck and conveying to dumping point approved by MCGM, unloading, spreading etc. complete. With all leads and lifts. (SSR 2022-23/ I-Deb1)		Cum.	
3.00 Providing Metres	9.	Providing and laying telephone black / Amba White / Cadbury brown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete. (SSR 2022-23/33.68) Add 5% For Corpn.			
		Total		Sqm.	
5.00 Square Metres	10.	Providing and fixing in position (as per 1868 / 1982) Aluminum sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 kg/Rmt. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 kg/Rmt.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer incharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net Shutter with stainless steel jail with all required screws and nuts etc, complete. With colour Anodising without box (SSR 2022-23/39.42) Add 5% For Corpn.			
		Total		Sqm.	
40.00 Square Metres	11.	Providing and laying vitrified rustic matt stone finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10mm thickness and			





		confirming to IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and cleaning etc. complete. (SSR 2022-23/33.44) Add 5% For Corpn.			
		Total		Sqm.	
4.00 Square Metres	12.	Providing and laying vitrified rustic matt stone finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm to 8 to 10mm thickness and confirming to IS. 15622-2006 (Group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and cleaning. etc. complete. (SSR 2022-23/ 33.45) Add 5% For Corpn.			
		Total		Sqm.	
6.00 Square Metres	13.	Glazed door:- Providing and fixing on site full ht. both side partly laminated partly GLAZED double door shutter at require location and having height more than 1.5meter made by using solid core commercial type door 35mm thick of the requisite manufacture viz Anchor/Century/Kenwood/Duro or equivalent generally confirming to I.S.303/I.S.710- 1980 finished with 1.5mm th. laminate matt/suede/fine line finished laminated pattern with grooves on both sides. Ant termite treatment to plywood and woodwork with ten years guarantee bond etc. including all leads & lifts etc. complete. The shutter shall be provided with 8 mm th. float glass of 15 x 60 cm of approved make or as directed with etching and lipping (BTC)/ moulding for fixing glass necessary lipping (BTC), molding, hardware, locks, handles, polishing etc as per Architect's Drawing a instructions of Engineer in Charge.  Approved Rate			
<b>Total (A) Work Portion Rs. :</b>					
<b>Total (A = Rs. :</b>					
<b>Add GST 18% Rs. :</b>					
<b>Total Rs. :</b>					
<b>Say Rs. :</b>					

