


SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020

Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Section/2026-27/156

14th August, 2026

SUB: Quotation for Site Development work near Home Science College Bldg at S.N.D.T. Women's University, Pune campus.

Madam/Sir,

Sealed quotations are invited for Quotation for "Site Development work near Home Science College Bldg at S.N.D.T. Women's University, Pune campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **17th September 2026**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

A) Technical Bid

- Detailed Company Profile (Contact details of contractor including address, phone number and email ID)
- Copies of Work Completion Certificates / Work Orders for similar works executed in the last three years.
- GST Registration Certificate (Self attested)
- PAN Card (Self attested)
- If GST is not applicable then declaration of the same.
- If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant
- Income Tax Return or Financial Statement of the last financial year or turnover 1.5 times of the civil work
- Undertaking stating that the contractor has not been blacklisted by any Government / Semi-Government organization.

B) Financial Bid

- Mentioning including all taxes
- If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,


Prof. Vilas D. Nandavadekar
Registrar
SNDT Women's University
Mumbai - 400 020.

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Site Development work near Home Science College Bldg at S.N.D.T. Women's University, Pune campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	60.00	Cum		
2	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	6.00	Cum		
3	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided,finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer etc. complete, With fine aggregate (Crushed sand VSI Grade)	13.00	Cum		
4	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	7.00	Cum		
5	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry	65.00	Sqm		

	surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.				
6	Providing and laying vitrified rustic matt stone finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm to 8 to 10mm thickness and confirming to IS. 15622-2006 (Group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and cleaning. etc. complete.	30.00	Sqm		
7	Providing and laying red soil levelling including all lead lift etc. Complete	60.00	Cum		
8	Providing and laying green lawn with all necessary material etc. complete.	350.00	Sqm		
9	Providing and fixing heavy duty inter locking concrete RUBBER MOULD GLOSSY PAVING BLOCKS of 60 millimeter thickness of having a strength of 400 Kilogram/sq.m of approved quality and shape on a bed of crushed sand of 25 to 30 millimeter thick including striking joints and cleaning etc. complete. (using 100% crushed sand)	75.00	Sqm		
10	Providing and casting in situ or precast tapering R.C.C. M-20 Barrier type Kerb without gutter (as per IRC 86 1983) embedded 125mm below ground level over M-10 PCC finished neatly with C.M. 1:2, setting the same in C.M. 1:2, including the required excavation in any strata and removing the excavated stuff any where in city and redoing the surface as specified and directed by Engineering In-charge. Using Concrete Batching and Mixing Plant	110.00	Rmt		
11	Supply of labour Mazdoor/ Dresser (Semi Skilled) for site cleaning and dismantling existing damaged masonry work including all lead and lift etc. Complete.	15.00	Day		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				