



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Estate Dept./2018-19/ (Not. 6)/134

September 11, 2018

Sub: Quotation of Construction of Ramp work at Main Arts & Commerce building at SNDT Women's University, Pune Campus

Madam/Sir,

Sealed quotations are invited for Construction of Ramp work at Main Arts & Commerce building at SNDT Women's University, Pune Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 28th September 2018.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Meena Kute
11.9.18
(Dr. Meena Kute)
Registrar (Addl. Charge)



SNDT WOMEN'S UNIVERSITY

1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

(Offer should filled on letter head)

Annexure A


To, :
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Construction of Ramp work at Main Arts & Commerce building at SNDT Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Providing Labour charger for site cleaning of ram including removing grass, jungle shrub and disposing off out of building promises etc complete.	4.00	Nos.		
2	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	6.5.00	Cum		
3	Providing internal cement plaster 25mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick or stone surfaces, in all positions including scaffolding and curing etc. complete.	48.00	Sqm		
4	Providing and filling in plinth and floor with constructors material/brought from outside and approved by Engineer incharge in layer of 15cm to 20cm including watering and compacting etc.	12.00	Cum		
5	Providing soling using 80 mm size trap metal in 15cm layer including filling voids with crushed sand/grill ramming. Watering etc complete.	7.00	Cum		
6	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, plywood/steel formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc.	6.00	Cum		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No.	Description	Qty	Unit	Rate	Amount
	complete. Including using with natural sand and curing, scaffolding etc complete.				
7	Providing and fixing 50mm diameter M. S. Pipe 16 G. in heavy quality for railing including cutting, fabricating, erecting and painting with one coat of anticorrosive paint and two coat of oil painting etc complete.	65.00	RM		
8	Providing and laying Antiskid Ceramic tiles of approved quality of size 30 cm x 30 cm and confirming to IS 15622-2006 (Group-B IIA) for antiskid flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.	19.00	Sqm		
9	Providing and applying two coats of exterior acrylic emulsion paint confirming to corresponding I.S. of approved manufacture and of approved colour to the plastered surface including cleaning, preparing at the plaster surface, applying primer coats scaffolding if necessary and watering the surface for two days etc complete.	83.00	Sqm		
Total Amount					

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable.