



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Estate Dept./2018-19/ (Not. 5)/132

September 11, 2018

Sub: Quotation of laying drainage pipe line work at SNDT Women's University, Pune Campus.

Madam/Sir,

Sealed quotations are invited for laying drainage pipe line work at SNDT Women's University, Pune Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 28th September 2018.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

MALS
11-9-18
(Dr. Meena Kute)
Registrar (Addl. Charge)



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for laying drainage pipe line work at SNDT Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete.	225.00	Cum		
2	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, plywood/steel formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete.	15.00	Cum		
3	Removing chock up old drainage pipe line cleaning and site cleaning	1.00	No.		
4	Providing and laying concrete pipes of I.S.NP. class of 300mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete. Removing earthen, stonewate pipe and stacking them as directed with all leads, lifts etc. complete.	130.00	RM		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No.	Description	Qty	Unit	Rate	Amount
5	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140 kg with frame etc complete.	14.00	Nos.		
Total Amount					

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of:Company

Signature Of the Proprietor

Date:

Note: enclose GST number, PAN number, declaration if GST is not applicable.